

# VIVEKANANDA MISSION MAHAVIDYALAYA

AT + P.O – CHAITANYAPUR \* HALDIA \* PURBA MEDINIPUR

*Quotation invite for Installation charge with materials for 45 KVA DG Set*

*Ref. No. – VMM/RUSA/ST/3/17*

Sl.No.	Items & Specification	Qty.	Unit	Rate per Unit including VAT & installation Charge (Filled by renderer)
1	Earth station complete by supplying 2" X 10' G.I. pipe charcoal, salt and complete by earth pit cover.	4	Nos.	
2	Earth strip with earth continuity 25 X 3 mm supply and laying complete	15	Mtrs.	
3	Supply and laying of 50 sqmm X 3.5 core aluminium armoured cable <b>(Havels-Make)</b> .	15	Mtrs.	
4	Copper Cable for Neutral Earthing-16sqmm	6	Mtrs.	
5	Cable End Termination	4	Nos.	
6	Change Over Switch -200amp <b>(Havels-Make)</b>	1	Nos.	
	Total			Rs.

Full Address & Contact Number :